
LEOTEK®

DT Series Traffic Signal Modules

8" and 12" Incandescent Look LED Balls & Arrows with Standard 15-Year Warranty

Leotek's DT Series Extended Life Traffic Signal Modules are specially designed to deliver extra-long life and provide perfect uniformity.

The patented, innovative optical technology of the DT Series LED Traffic Signal Module can help provide dramatic savings on energy and maintenance costs.



DT products meet all ITE Standards and are approved by many major United States Departments of Transportation and listed on numerous "Approved Products" Lists.

Features:


- Standard 15-Year Warranty
- Engineered for superior thermal management
- Enhanced uniformity
- Intertek ETL verified
- Meets and/or exceeds all ITE standards
- Easy installation into existing signal housings
- Overmolded electrical connectors provide fully-weatherized seal





DT Series Traffic Signal Modules 8" and 12" Incandescent Look LED Balls & Arrows with Standard 15-Year Warranty





Model Specifications and Ordering Options

| Operating Temperature:-40°F to 165°F (-40°C to 74°C) | Turn-On/Turn-Off Time: < 75msec | |
|--|--|--|
| Operating Voltage: 80- 135Vac | Turn-Off Voltage: > 35Vac | |
| Power Factor: > 0.90 | Total Harmonic Distortion (THD): < 20% | |

| DT BALLS | Model Number and Color | Wattage Drawn | Voltage | Dominant Wavelength | Maintained Intensity (cd) Min. | Standard | |
|----------|---------------------------|------------------|-----------|------------------------|-----------------------------------|--------------|--|
| | 8 inch ball | | | | | | |
| | TSL-08R-DT-A1 | 6.1 | 80-135Vac | 626 | 165 | ITE 2005/ETL | |
| | TSL-08Y-DT-A1 | 6.1 | 80-135Vac | 589 | 410 | ITE 2005/ETL | |
| | TSL-08G-DT-A1 | 6.2 | 80-135Vac | 500 | 215 | ITE 2005/ETL | |
| | 12 inch ball | | | | | | |
| | TSL-12R-DT-A1 | 6.2 | 80-135Vac | 626 | 365 | ITE 2005/ETL | |
| | TSL-12Y-DT-A1 | 7.9 | 80-135Vac | 589 | 910 | ITE 2005/ETL | |
| | TSL-12G-DT-A1 | 6.1 | 80-135Vac | 500 | 475 | ITE 2005/ETL | |

| SI | Model Number and Color | Wattage Drawn | Voltage | Dominant Wavelength | Maintained Intensity (cd) Min. | Standard |
|--------|---------------------------|------------------|-----------|------------------------|-----------------------------------|--------------|
| ARROWS | 12 inch arrow | | | | | |
| | TSL-12RA-DT-A1 | 6 | 80-135Vac | 626 | 58.4 | ITE 2007/ETL |
| DT | TSL-12YA-DT-A1 | 10 | 80-135Vac | 589 | 145.6 | ITE 2007/ETL |
| | TSL-12GA-DT-A1 | 6.8 | 80-135Vac | 500 | 76.0 | ITE 2007/ETL |

Note: Tinted lens standard, clear lens optional. When ordering clear lens, please add "-CLR" to model number. Both tinted and clear lens are Intertek ETL Verified.



DT Signals Information Sheet 3-29-2022

